



भारतीय लोक प्रशासन संस्थान

इन्द्रप्रस्थ एस्टेट, रिंग रोड, नई दिल्ली-110002

INDIAN INSTITUTE OF PUBLIC ADMINISTRATION
INDRAPRASTHA ESTATE, RING ROAD, NEW DELHI-110002 (INDIA)

Short Notice Inviting Quotation

29/06/2021

M/s _____

Subject: - SITC of power cable in IIPA.

Sir,

Sealed quotations are invited from reputed firms on behalf of the Director General IIPA for the above work in IIPA. Interested Company/Firm/Contractor may drop the quotation in the Tender Box in the Room of Executive Engineer along with an E.M.D. of Rs. 30,000/- only in the shape of cash/DD by 05/07/2021 up to 3.00 PM. and shall be opened by the Committee constituted for the purpose. The rates quoted should be clearly mentioned with taxes if any. The details of the work are following:-

Schedule of Items					
S.No.	Item Description	Unit	Qty.	Rate in Rs.	Amount in Rs.
A	Supplying & laying of following 1100 volt grade XLPE insulated PVC sheathed Aluminium/Copper conductor armoured cables as per specification in existing trenches, pipes,cable tray, clamped to wall with suitable clamps including, saddles fixing bolts, testing and commissioning complete in all respect as required as per site conditions.				
	3.5 core 240 sq. mm Al arm.(3 Run * 260 RM = 780 RM)	Meter	780		
B	Supplying and making Cable end termination of the following XLPE insulated PVC sheathed Aluminium conductor armoured cables of 1100 volt grade including supplying and fixing of bimettalic crimping lugs, Single compression glands and commissioning complete in all respect as required as per site conditions.				
	3.5 core 240 sq. mm Al arm.	Each	12		

SEAL AND SIGNATURE OF THE FIRM

C	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm/as required, below ground level)including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required (For NTRI building)				
	200 mm dia (OD-200 mm & ID-175 mm nominal)	Meter	240		
	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. in the existing trench, complete as required (for IIPA Bhawan)				
	200 mm dia (OD-20 mm & ID-175 mm nominal)	Meter	400		
D	Constructing brick masonry manhole in mortar 1:4 (1 cement : 4 coarse sand) R.C.C. top slab with 1:2:4 mix (1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement:4 coarse sand:8 graded stone aggregate 20 mm nominal size) finished with floating coat of neat cement and making channels in cement concrete 1:2:4: (1 cement:2 coarse sand:4 graded stone aggregate 20mm nominal size) finished with floating coat of neat cement complete as per standard design :-				
	Inside size 75 x 40 cm and 60 cm deep including SFRC Cover with frame (Heavy duty).	Each	15		
E	SITC of LT panel with 800 A, 4 Pole, 50KA MCCB - (MTX1)make - ABB / L&T with extended rotary handle and spreader terminal duly enclosed in 14 SWG CRCA sheet encloser of size 2.0 meter x 1.0 meter x 0.5 meter floor mounted on base channel, having all in one multifunctional meter, indicators with led lights ,CTs one set and earthing and as required.	Each	1		
F	Chipping and making same finish of 300*750 MM of road for laying of cable	Rft	150		
Total					
GST @ _____%					
Grand Total					

SEAL AND SIGNATURE OF THE FIRM

Terms and Conditions :-

1. The Institute has right to reject any or all the quotations without assigning reasons.
2. The rates should be clearly mentioned inclusive of all the taxes.
3. The firm must have a valid Electrical contractor licence/Registered with any power utility/CPWD/any Govt./Semi Govt. Organization.
4. The firm shall inspect the site before quoting.
5. The bidder has to submit an interest free EMD of Rs.30,000/- by way of cash or on DD of any Nationalized Bank in favour of Indian Institute of Public Administration, Payable at New Delhi. The EMD of unsuccessful bidders will be refunded within 15 days of award of the work and the EMD of the successful bidder will be retained & will be paid after completion of the work.
6. Completion time for work is 21 days from the issue of work order.
7. Penalty 0.01% of the awarded amount per day, subjected to maximum 10% shall be charged, in case the work is not completed on time.
8. Payment will be made after completion of the work satisfactorily.
9. Payment shall be made on actual measurement basis.
10. 5 % security will be withheld for 6 month after satisfactory completion of the job as defect liabilities.
11. If any clarifications about the work, Contractor may contact "Electrical Supervisor, 2nd floor of IIPA Office Building, tel. 23468399.

Yours Sincerely,



(H.O. Goel)
Executive Engineer

SEAL AND SIGNATURE OF THE FIRM