



# भारतीय लोक प्रशासन संस्थान

इन्द्रप्रस्थ एस्टेट, रिंग रोड, नई दिल्ली-110002

INDIAN INSTITUTE OF PUBLIC ADMINISTRATION  
INDRAPRASTHA ESTATE, RING ROAD, NEW DELHI-110002 (INDIA)

Short Notice Inviting Quotation

17/03/2020

M/s \_\_\_\_\_

Subject: - SITC of power cable in IIPA .

Sir,

Sealed quotations are invited from reputed firms on behalf of the Director IIPA for the above work in IIPA. The quotations should reach the Electrical Supervisor by 20/03/, 2020 and shall be opened by the Committee constituted for the purpose. The rates quoted should be clearly mentioned with taxes if any. The details of the work are following:-

| Schedule of Items |  |       |     |                |                  |
|-------------------|--|-------|-----|----------------|------------------|
| S.No.             | Description  | Unit  | Qty | Rate Incl. GST | Amount Incl. GST |
| 1                 | Supply, termination & testing of (Havells/Finolex etc. make)1.1kV grade, 4 Core,300 Sq. mm. XLPE insulated, and overall sheathed, stranded aluminum conductor, flat steel strip/wire armored cables The cable shall bear ISI certification mark, Dismantling of old cable and repairing of walls, concrete road & concrete floor as required | Metre | 125 |                |                  |
| 2                 | Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.   | Metre | 110 |                |                  |
| 3                 | Supply, termination & testing of (Havells/Finolex etc. make)1.1kV grade, 4 Core,300 Sq. mm. XLPE insulated, and overall sheathed, stranded aluminum conductor, flat steel strip/wire armored cables The cable shall bear ISI certification mark  | Metre | 125 |                |                  |

Date:


(Name, Signature and Seal of Firm)

|       |   |       |     |  |  |
|-------|---|-------|-----|--|--|
| 4     | Laying of one number additional PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc as required. | Metre | 110 |  |  |
| 5     | Supply Laying of GI Pipe for road crossing 3" B Class, Jindal etc. in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.make as required   | Metre | 12  |  |  |
| 6     | Supply Laying of GI Pipe for road crossing 3" B Class, Jindal etc. in ground in existing trench, sand cushioning as required  | Metre | 12  |  |  |
| Total |   |       |     |  |  |

**Terms and Conditions :-**

1. The Institute has right to reject any or all the quotations without assigning reasons.
2. The rates should be clearly mentioned inclusive of all the taxes.
3. The firm must be registered with BSES/NDPL/other electricity board/Nigam and must enclose proof of the same.
4. The firm shall inspect the site before quoting.
5. Completion time for work is 08 days from the issue of work order.
6. Penalty 0.01% of the awarded amount per day, subjected to maximum 10% shall be charged, in case the work is not completed on time.
7. Payment will be made after completion of the work satisfactorily.
8. Payment shall be made on actual measurement basis.
9. 5 % security will be withheld for 1 year after satisfactory completion of the job as defect liabilities.
10. If any clarifications about the work, Contractor may contact "Electrical Supervisor, 2<sup>nd</sup> floor of IIPA Office Building, tel. 23468399

Yours Sincerely,

  
 (Ashok Sharma) 17/03/2020  
 Electrical Supervisor

Date:

(Name, Signature and Seal of Firm)