



भारतीय लोक प्रशासन संस्थान

इन्द्रप्रस्थ एस्टेट, रिंग रोड, नई दिल्ली-110002

INDIAN INSTITUTE OF PUBLIC ADMINISTRATION
INDRAPRASTHA ESTATE, RING ROAD, NEW DELHI-110002 (INDIA)

Notice Inviting Quotation

08/06/2020

M/s _____

Subject: - SITC of power cable in IIPA .

Sir,

Sealed quotations are invited from reputed firms on behalf of the Director IIPA for the above work in IIPA. The quotations should reach the Electrical Supervisor by 23/06/, 2020 and shall be opened by the Committee constituted for the purpose. The rates quoted should be clearly mentioned with taxes if any. The details of the work are following:-

Schedule of Items					
S.No.	Description	Unit	Qty	Rate Incl. GST	Amount Incl. GST
1	Supply, termination & testing of (Havells/Finolex etc. make) 1.1kV grade, 4 Core, 300 Sq. mm. XLPE insulated, and overall sheathed, stranded aluminum conductor, flat steel strip/wire armored cables. The cable shall bear ISI certification mark, Dismantling of old cable and repairing of walls, concrete road & concrete floor as required.	Metre	125		
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.	Metre	110		
3	Supply, termination & testing of (Havells/Finolex etc. make) 1.1kV grade, 4 Core, 300 Sq. mm. XLPE insulated, and overall sheathed, stranded aluminum conductor, flat steel strip/wire armored cables. The cable shall bear ISI certification mark.	Metre	125		

Date:

(Name, Signature and Seal of Firm)

4	Laying of one number additional PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc as required.	Metre	110		
5	Supply Laying of GI Pipe for road crossing 3" B Class, Jindal etc. in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.make as required	Metre	12		
6	Supply Laying of GI Pipe for road crossing 3" B Class, Jindal etc. in ground in existing trench, sand cushioning as required	Metre	12		
Total					

Terms and Conditions :-

1. The Institute has right to reject any or all the quotations without assigning reasons.
2. The rates should be clearly mentioned inclusive of all the taxes.
3. The firm must be registered with BSES/NDPL/other electricity board/Nigam and must enclose proof of the same.
4. The firm shall inspect the site before quoting.
5. Completion time for work is 08 days from the issue of work order.
6. Penalty 0.01% of the awarded amount per day, subjected to maximum 10% shall be charged, in case the work is not completed on time.
7. Payment will be made after completion of the work satisfactorily.
8. Payment shall be made on actual measurement basis.
9. 5 % security will be withheld for 1 year after satisfactory completion of the job as defect liabilities.
10. If any clarifications about the work, Contractor may contact "Electrical Supervisor, 2nd floor of IIPA Office Building, tel. 23468399

Yours Sincerely,



(Ashok Sharma)

Electrical Supervisor

10/06/2020

Date:

(Name, Signature and Seal of Firm)